4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Mail Lock-up building in the compound of the existing Jail at Chikmagalur," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Royalty to be paid to Government will have to be borne by the contractor.

No.	*Items of work*	*Per*	*Quantity*
1.	Earthwork, (excavation and filling basement)	C. yd.	126
2.	Filling (concrete in lime mortar)	C. ft.	562
3.	Filling foundation and basement (burnt stone in lime mortar)	,,	4,252
4.	Burnt brick in lime mortar (superstructure)	,,	8,502
5.	Do (arch work)	,,	136
6.	Burnt stone slabs, dressed	S. ft.	1,153.
7.	Burnt brick in chunam, parapet wall, with cornice work chunam plastering, etc., complete	R. ft.	31
8.	Burnt brick in chunam cornice work, with plastering, etc., complete 12"	,,	353
9.	Burnt brick in chunam cornice work, with plastering, etc., complete 9"	,,	36
10.	Partico above pediment work, as per plan	Lump sum	
11.	Chunam plastering	Sqr.	113·13
12.	Whitewashing two coats	,,	83·00
13.	Color-washing do	,,	36·44
14.	Teakwood work wrought and put up with wood oiling ...	C. ft.	176·65
15.	Flat terrace roof, complete	Sqr.	5·06
16.	Roofing with 1st class Mangalore tiles with teak reepers, etc., complete	,,	24·20
17.	Ordinary Mangalore ridge tiles set in mortar	R. ft.	110
18.	Teakwood entrance doors with panelled shutters, plank $1\frac{1}{2}$" thick and strong hinges, bolts and locks, etc., complete...	S. ft.	60
19.	Teakwood doors with $\frac{2}{3}$ battened and $\frac{1}{3}$ iron-barred shutters, hinges, locks, etc., complete	,,	227
20.	Teakwood windows, outside-battened shutters, inside-glazed shutters with $\frac{7}{8}$" diameter iron bars, iron works, etc., complete	,,	108
21.	Teakwood ventilators with iron bars 1" diameter and perforated zinc sheet, iron work, etc., complete	,,	87
22.	Painting to doors, windows and ventilators	Sqr.	10·72
23.	Flooring with Cuddapah slabs on 3" concrete bed and cement pointing, etc., complete	,,	0·48
24.	Flooring with 1st class Mangalore tiles on 3" concrete bed and cement pointing, etc., complete	,,	18·10
25.	Cement pointing to basement	,,	4·42
26.	Rain water zinc down pipes (4" diameter)	R. ft.	90
27.	Teakwood plank ceiling, $\frac{1}{2}$" thick, with oiling, etc., complete...	Sqr.	17·66
28.	Chunam quoin work	Lump sum	
	Deduct—		
	Amount realized by the sale of old materials	Do	

R. S. NAVARATNA,
Executive Engineer.

CHITALDRUG DIVISION.

Abstract Notification.

It is hereby notified that sealed tenders for constructing a Revenue Sub-Division Office with out-houses at Davangere, will be received by the Executive Engineer, Chitaldrug Division, up to 3rd March 1912.

For particulars, *vide* pages 256 and 257, Part II of the *Mysore Gazette*, dated 15th February 1912.

C. KRISHNA IYENGAR,
Executive Engineer.